

Getting Your Building Back to Operational

Before your teams get back into action, you want to make sure that premises are ready to go. Team with Harris on any of the following if you need assistance.



Clean Equipment and Control Panels

For ventilation systems, clean down any locations where people may have had an opportunity to interact with them. This could be outside the facility such as at louvers.



Sanitize Equipment

Within systems, spray disinfectants can be used to disinfect internal surfaces such as drain pans, coil surfaces etc.




Check Water Chemistry in Any Open Water Systems

When systems are not running, localized chemistry changes or fouling issues can occur in water systems which should be checked before operations begin.



Flush Through Domestic Water Systems

Domestic water systems should be flushed through to ensure there are no air pockets.



Change Filters

It is recommended to change out the filters before restarting operations. Operations teams may want to upgrade lower grade filters to a minimum of MERV 13.



Ensure All Systems Are Fully Operational

It is important that there has been enough run time of the equipment to get facilities back to their regular operation before re-opening facilities.

Unsure of how your building is performing during this downtime? Let us help.

Harris Telemetry is a service which can provide remote system monitoring to help evaluate your facilities service needs and identify issues early.